

ADDENDUM No. 1

To

Contract Documents, Specifications, and Plans

For

**AMERICAN FORK CITY
UPPER WEST TANK REHAB PROJECT**

July 9, 2019



ADDENDUM No. 1
To
Contract Documents, Specifications, and Plans
For
American Fork City
Upper East Tank Rehab Project
July 9, 2019

These Contract Documents, Specifications, and Plans are hereby revised to include the following changes. Contractors bidding the project shall conform to these revisions and acknowledge receipt of this Addendum on Page 1 of the Bid Form (003000-1).

GENERAL

The day of the bid opening is hereby extended to July 11, 2019 at 2:00 pm.

The question and answer period is hereby extended to July 9, 2019 at 12:00 pm.

SPECIFICATIONS

Change Section 001000 Information for Bidders and other related sections.

“Fifty-one (51) percent of all work completed shall be performed by the General Contractor.” Is no longer required.


Clarification Drilling through existing rebar to install new rebar cage is not allowed. Radar locating is not required. If rebar is encountered during drilling then move to the side and re-drill.

Minimum shotcrete thickness is 4 inches per plan detail with 2 inch minimum outside cover on rebar. No specific finish is required on shotcrete.

Addendum #1 is hereby approved and issued on July 9, 2019.

By Horrocks Engineers

John E. Schiess, P.E.



END ADDENDUM